BANGALORE DIVISION.

Abstract Notification dated 18th October 1911.

The attention of the public is invited to the Notification dated 16th October 1911. calling for tenders for restoring the breached Akkur Anikat and tank Registered No. 125, Channapatna Taluk, published on page 1208, Part II of the *Mysore Gazette* dated 19th October 1911.

V. R. NIJAGAL,
Executive Engineer.

KOLAR DIVISION.

NOTICE.

It is hereby notified that as dead rats and squirrels were found in the 2nd class travellers' bungalow at Chikballapur, the building is unfit for occupation till it is cleaned and disinfected, about which another notice will be published.

B. B. GARUDACHARIAR,
Executive Engineer.

MYSORE DIVISION.

Dated 14th October 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 15th November 1911, for constructing a new tank at Hairige across the Vadli stream in Hunsur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 2 and 5 P.M

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for constructing a new tank at Hirige in Hunsur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities for constructing a new tank at Hirige across the Vadli stream, Hunsur Taluk, Mysore District.

Items of work.	*Per*	*Quantity.*
Bund—R. L. 80·00, *Top width* 15; *Front slope* 2 *to* 1 *and* 1½ *to* 1, *Rear slope* 2 *to* 1. *R. L. of Revetment* 77·00.		
1. Top soil to be removed from seat of bund and used for the rear slope	C. yd.	16·975
2. Removing sand and silt	„	7·959
3. Cutting puddle trench	„	9·018
4. Excavation for core wall in river bed rocky soil ...	C. yd.	33
5. Stone in surki mortar	C. ft.	1,559
6. Earthwork to bund, with a mixture of ·2 clay and one gravel	C. yd.	1,71,515
7. Rough stone revetment including 1½ mile lead (as per new stone work table)	C. yd.	16,501
8. Puddle work	C. yd.	9,018
9. Carting and consolidating earth from weir cutting ...	C. yd.	42,460
10. Gravel backing	„	5,218
11. Dry stone toe wall	„	2,817